


Scale 1 : 50

0 1 2 4m

GENERAL NOTE:

Existing wall ties to be checked during demolitions to confirm structural integrity

SPECIFICATION NOTES:

PRELIMINARIES:

If the works are commenced prior to receipt of the building control approval notice, it will be the full responsibility of the contractor to inform the building control office of this intention. No responsibility will be accepted by the Agent / Designer for consequences arising out of failure to do so.

No liability will be accepted for any information used or copied in whole or in part for use in projects other than that of which this specification form part.

It is the clients responsibility to contact their insurance broker, in advance, to arrange the necessary insurance cover for the building and its contents for the duration of the works.

All works to be carried out with the minimum possible disturbance to the employer. Contractor to verify all dimensions on site and report any discrepancies immediately. Noted dimensions to be followed in preference to scaled dimensions. Specialist suppliers will be responsible for checking all relevant dimensions on site prior to all fabrications.

Provide adequate dust screening to opening between works area and remainder of house. All works to be completed in accordance with current building regulations whether expressly detailed on drawings or not.

The contractor shall establish the position of all overhead and underground services relating to works and make such information available to all disciplines on site as required under current health and safety regulations.

Vegetable matter such as turf and roots should be removed from the ground to be covered by the building at least to a depth to prevent later growth. The harmful effect that vegetation roots may have on the building should be assessed.

Any field drains uncovered during the course of the works to be re-routed to discharge to existing outfall.

MATERIALS AND WORKMANSHIP:

Workmanship generally to comply with the contents of the BSI Codes of Practice BS 8000:Parts 1 to 16, Workmanship on Building Sites.

All structural timbers to be clearly marked KD (Kiln Dried) C16 Grade or C24 Grade as per BS 5268: Part 2 1991 located as shown on drawings and details

BUILDING CONTROL INSPECTIONS:

The contractor is responsible for issuing the building control inspection cards, or otherwise contacting building control at the relevant stages as indicated on these cards. Should the works be commenced prior to receipt of such cards then the contractor must notify in writing, or otherwise contact building control 2 working days prior to reaching the following stages:

1 Excavation of foundation trenches (prior to placing of concrete)
2 Placing of foundation concrete (prior to blockwork)
3. After placing and compacting of subfloor, hardcore and radon protection (prior to placing concrete subfloor)
4. External drainage (prior to backfilling)
5. External drainage (following backfilling)
6. Completion of structural carcass (prior to plasterboarding, completion of works or occupation).

Should the contractor fail to correctly inform building control at above stages, then the costs of any work due to a subsequent request by the building control inspector to open up, or otherwise expose works requiring inspection, will be borne by the contractor.

OPERATIONS AND MAINTENANCE INSTRUCTIONS:

Manufacturers to provide sufficient information to the building owner regarding the energy efficient operation and maintenance of fixed building services in a readily understandable manner.

STRIP FOUNDATIONS:

New foundations to bear at underside of existing foundations as minimum.

Bearing stratum to have 100KN/m 2 capacity.

Based on suitable ground bearing foundations to be:
- 600mm wide x 300mm deep (unreinforced) for external cavity walls

Depth and size are subject to direction on site when ground conditions are determined. Minimum ground cover in any instance to be 500mm. Foundations designed to be adequate if site bearing is type 4 or better in accordance with Building Regulations NI 2012 Technical Booklet D, Section 4 Part 4E Diagram 4E 1. If suitable bearing not found at normal depth a foundation design based on soil investigation report will be required.

EXTERNAL CAVITY WALL CONSTRUCTION:

NEW CAVITY WALLS - BLOCK

350mm cavity wall system made up of 100mm dense concrete block (min 7.3N/mm 2) external leaf finished with 20mm thick cladding on 50mm battens, 100mm Thermawall TW50 by Kingspan or equal approved partial insulation board in 150mm cavity. Internal leaf to be 100mm dense concrete block (min 7.3/mm 2). U-value required for external walls 0.28W/m2K U-value achieved 0.17W/m 2K.

NEW CAVITY WALLS - BRICK

350mm cavity wall system made up of Brick external leaf, 100mm Thermawall TW50 by Kingspan or equal approved partial insulation board in 150mm cavity. Internal leaf to be 100mm dense concrete block (min 7.3/mm 2). U-value required for external walls 0.28W/m 2K, U-value achieved 0.18W/m 2K

External Wall Finish:

Neo timber deluxe cladding board on external side or approved equal TBC by client.

Internal Wall Finish:

Sand and cement bonding coat with plaster skim finish. Painted to client spec.

EXISTING CAVITY WALLS

All retained existing external cavity walls to be cladded with 120mm external insulation board and finished in 20mm render.

WALL TIES:

Cavity wall ties should be austenitic stainless steel in accordance with BS EN 845-1 and DD140 2. Wall ties should have a horizontal spacing of 900 and a vertical spacing of 450mm, which is equivalent 2.5 ties per square metre. Wall ties should also be spaced not greater than 300mm apart vertically within a distance of 225mm from the vertical edge of any opening, movement joint and roof verge.

Wall ties to be Ancon Staifix RT2 General Purpose Wall Tie Type 2 Tie to PD 6697 or equal approved. Wall tie length to suit cavities 150mm wide. Wall ties complete with insulation retaining discs.

INTERNAL WALL CONSTRUCTION:

STUD WALLS:

12.5mm Gyproc Soundbloc Board providing minimum mass per unit area of 10Kg/m2. Stud cavities to be filled with mineral wool insulation providing minimum density of 10kg/m3.

LATERAL SUPPORT:

Internal block walls to be strapped to ceiling joists with 30x5mm Galv MS restraint straps @ max 2m centres. Straps turned down into wall 100mm min.

NEW FLOOR CONSTRUCTION

New beam and block floor slab make up consisting of 50mm RTU screed poured over underfloor heating pipes, on 150mm insulation screed over DPM layer, on 150mm beam and block floor structure suspended over 50mm screed on Visqueen Radon R400 barrier laid on well compacted earth. U-value required for existing renovated floors 0.25W/m 2K. U-Value achieved 0.22W/m 2K.

EXISTING REPLACEMENT FLOOR CONSTRUCTION

Existing area of floor indicated on plan to be demolished and removed to make way for new beam and block floor slab make up consisting of 50mm RTU screed poured over underfloor heating pipes, on 150mm insulation screed over DPM layer, on 150mm beam and block floor structure suspended over 50mm screed on Visqueen Radon R400 barrier laid on well compacted earth. U-value required for existing renovated floors 0.25W/m 2K. U-Value achieved 0.22W/m 2K.

NEW CEILINGS:

New ceilings to be provided as identified on Ground Floor Ceiling Plan. Ceiling finish to be 12.5mm Gyproc Soundbloc Board providing min mass per unit area of 10kg/m. Provide absorbent layer of mineral wool between joists to first floor level of minimum thickness 100mm & minimum density 10kg/m3. All gaps are to be filled around abutments with internal walls to avoid air paths between rooms.

FLAT ROOF CONSTRUCTION:

Timber joists supported off joists hangers and steel frame, designed to engineers specification. 'Sika-Trocal' or equal approved adhered single ply roofing membrane, on 120mm Kingspan Thermaroof overlay, on Vapour Barrier Layer, on 18mm plywood deck, on tapered firing pieces fixed over 50mm x 195mm timber joists. Roof to be laid to minimum 1:80 fall in direction shown on drawings.

NEW EXTENSION FASCIA/SOFFIT BOARDS :

Provide standard treated timber soffit and fascia boards in preparation for uPVC finish. Finished colour to be white.

EXISTING FASCIAS, SOFFITS & TUDOR PANELLING :

All existing fascias, soffits & timber panelling to be prepared before receiving new painted finish, colour TBC.

RAINWATER GOODS:

Scupper drains to be formed into parapet walls linked to 68mm diameter downpipes connected to outlets within concealed gutter at locations identified on plan and terminated into new bottle gullies at ground level. Colour of downpipes to match existing. Ensure watertight connection between outlet in concealed gutter and downpipe.

EXTERNAL DOORS:

New sliding doors from Sunroom and Casual Dining to be aluminium triple glazed frame - external frame colour RAL 7021.

Dining room to have new Aluminium triple glazed framed double doors with side light on either side - external frame colour RAL 7021

Style of doors to TBC by client. Doors to achieve u-value of 1.8W/m ^{2}K or better.

INTERNAL DOORS:

All existing internal doors to be replaced with new. Door to be supplied by client and fitted by contractor.

SKIRTING BOARDS:

All existing skirting boards to be replaced with new moulded skirting. Skirting to be primed and painted. Colour and style of skirting TBC by Client.

WINDOWS:

All new windows to be Alu-Clad triple glazed windows with argon gas filled cavities to achieve u-value of 1.6W/m ^{2}K or better. Refer to window schedule for details.

EXTERNAL WINDOW SILLS:

New sills to be precast concrete stool ended sills approx 285x140x90mm to match existing retained sills. Ensure dpc is applied to stool ends

INSULATED STEEL LINTELS:

External lintels where indicated to support new structural openings to be insulated steel lintels by Keystone Lintels. Lintel sizes as per Keystone spec.

External lintels to have Visqueen or equal stepped DPC fitted over lintel with suitable perpends at 900mm centres.

All lintels to have minimum bearing of 150mm at both ends on mortar bedding to manufacturers requirements.

CAVITY TRAYS & LEAD FLASHING:

Prevent damp penetration where new cavity walls abut existing walls by providing Type B Insulated Vertical DPC Cavitray by Cavity Trays UK or equal approved supplier. Vertical cavity trays to be adequately chased into existing external outer wall leaf.

Provide stepped DPC cavity trays along new roof abutment with existing cavity wall to protect against rainwater ingress. To be installed in strict accordance with manufacturers instruction.

New flat roof to be suitably flashed 150mm min along abutment with existing wall with Code 4 Lead flashing. Lead flashing to be stepped and chased under stepped DPC cavity trays by 25mm. Flashing wedged into place and joints pointed. Patination oil to be used on all lead flashings to finish to prevent lead carbonate forming on lead and staining adjacent materials.

Combined proprietary stepped DPC cavity trays complete with flashing can be used by cavity trays UK or equal approved supplier.

DAMP PROOFING:

All dpcs and dpms shall be Visqueen or equal approved. DPC to be laid horizontally in all external walls on a level bed of mortar at minimum 150mm above finished ground level. All joints between lengths must have a min of 100mm overlap, fully supported and sealed using dpc joint supports and dpc jointing tape.

DPC to be provided at all heads, under all window sills and at door and window jambs in external walls.

DPC and DPM to be laid in accordance with BS743 and manufacturers instructions.

REV:	DATE:	COMMENTS:	DRWN	CHKD
P08	15.08.25	CLIENT ISSUE	OSE	JPG
P07	06.08.25	ISSUED TO BUILDING CONTROL	OSE	JPG
P06	23.07.25	ISSUED TO CONTRACTOR	OSE	JPG
P05	18.07.25	ISSUE FOR CLIENT REVIEW	OSE	JPG
P04	30.06.25	REVISED FOR WINDOW SUPPLIER	OSE	JPG
P03	20.06.25	ISSUED TO STRUCTURAL ENGINEER	OSE	JPG
P02	13.06.25	ISSUED FOR WINDOW SUPPLIER	OSE	JPG
P01	04.06.25	ISSUED FOR REVIEW	OSE	JPG

DRAWING STATUS:

PRELIMINARY

PROJECT:

DRAWING TITLE:

GROUND FLOOR PLAN

CLIENT:			DATE:	STATUS:
			FEB 2025	N/A
	DRAWN BY:	CHECKED:	SCALE:	SHEET SIZE:
25/102	MEO	JPG	1 : 50	A1
DRAWING NUMBER:				REVISION:
25-102-A100				P08